

Subdivisional Lines, T 5 N R 35 E W M.

Chains	<p>I run</p> <p>W. on true line bet. Secs. 26 & 35.</p> <p>Course S.89°39'W.</p> <p>39.92 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits; raised mound, as per instructions.</p> <p>79.85 To post Cor. of Secs. 26, 27, 34 & 35.</p> <p>Land; gently rolling.</p> <p>Grass good.</p> <p>Soil; 2nd rate.</p>
	<p>N. bet. Secs. 26 & 27.</p> <p style="text-align: right;">Var.21°E.</p> <p>40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits; raised mound, as per instructions.</p> <p>80.00 Set post Cor. for Secs. 22, 23, 26 & 27. Drove charred stake; dug pits; raised mound, as per instructions.</p> <p>Land; gently rolling.</p> <p>Grass good.</p> <p>Soil; 2nd rate.</p>
	<p>E. on random bet. Secs. 23 & 26.</p> <p>24.60 Dry creek, 25 lks. wide, course W. of N.</p> <p>40.00 Set temp. $\frac{1}{4}$ Sec. post.</p> <p>79.74 Intersect N. & S. line, 20 lks. S. of post; from which I run</p> <p>W. on true line, course S.89°51'W.</p> <p>39.87 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits; raised mound as per instructions.</p> <p>79.74 To post Cor. for Secs. 22, 23, 26 & 27.</p> <p>Land; rolling.</p> <p>Grass good.</p> <p>Soil; 2nd rate.</p>
	<p>N. bet. Secs. 22 & 23.</p> <p style="text-align: right;">Var.21°E.</p>