

## Subdivisional Lines, T 5 N R 35 E W M.

Chains	
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits; raised mound as per instructions.
80.00	Set post Cor. for Secs. 14, 15, 22 & 23. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Grass good. Soil; 2nd rate.
E. on random bet. Secs. 14 & 23.	
9.94	Dry Creek, 25 lks. Wide, course W. of N.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
72.75	Road, course W. of N.
80.00	Intersect N. & S. line, 28 lks. N. of post; from which, I run W. on true line, course N.89°48' W.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	To post Cor. for Secs. 14, 15, 22 & 23. Land; rolling. Good grass. Soil; 2nd rate.
N. bet. Secs. 14 & 15. <span style="float: right;">Var. 21° E.</span>	
6.50	Rail fence, E. & W.
14.50	Dry creek, course N.W.
27.00	Leave field.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits; raised mound, as per instructions.
80.00	Set post Cor. for Secs. 10, 11, 14 & 15. Drove charred stake; dug pits and raised mound, as per instructions. Land; rolling. Soil; good 2nd rate. Some willow & birch on Dry Creek.