

Subdivisional Lines, T 5 N R 35 E W M.

Chains	N. on random bet. Secs. 2 & 3. Var. 21°E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.12	Intersect E. & W. Tp. line, 10 lks. E. of post; from which I run S.00°04' E. on true line.
40.12	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.12	To post Cor. for Secs. 2, 3, 10 & 11. Land; rolling. Grass good. Soil; 2nd rate.
<hr/>	
	N. bet. Secs. 33 & 34.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits; raised mound, as per instructions.
56.85	Road, Walla Walla Road, course E. of N.
80.00	Set post Cor. for Secs. 27, 28, 33 & 34; drove charred stake; dug pits & raised mound, as per instructions. Land; gently rolling. Grass good. Soil; 2nd rate.
<hr/>	
	E. on random bet. Secs. 27 & 34.
9.00	Road. course E. of N.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.10	Intersect N. & S line, 25 lks. N. of post; from which I run W. on true line, course N.89°49' W.
40.05	Set post; drove charred stake; dug pits & raised mound, as per instructions.
80.10	To post Cor. for Secs. 27, 28, 33 & 34. Land; rolling. Grass good. Soil; 2nd rate.