

Subdivisional Lines, T 5 N R 35 E W M.

Chains

N. bet. Secs. 27 & 28.

Var. 21°E.

40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 21, 22, 27 & 28; drove charred stake; dug pits & raised mound, as per instructions.

Land; rolling.

Grass good.

Soil; 2nd rate.

E. on random bet. Secs. 22 & 27.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

79.64 Intersect N. & S. line, 20 lks. S. of post; from which, I run

W. on true line, course S.89°51'W.

39.82 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

79.64 To post Cor. for Secs. 21, 22, 27 & 28. Drove charred stake; dug pits & raised mound, as per instructions.

Land; rolling.

Grass good.

Soil; 2nd rate.

N. bet. Secs. 21 & 22.

Var. 21°E.

40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits; raised mound, as per instructions.

80.00 Set post Cor. for Secs. 15, 16, 21 & 22; drove charred stake; dug pits & raised mound, as per instructions.

Land; gently rolling.

Grass good.

Soil; 2nd rate.

E. on random bet. Secs. 15 & 22.

40.00 Set temp. $\frac{1}{4}$ Sec. post.