

Subdivisional Lines, T 5 N R 35 E W M.

Chains

N. bet. Secs. 9 & 10.

Var. 21°E.

40.00 Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 3, 4, 9 & 10. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken.

Soil; good 2nd rate.

Grass very good.

E. on random bet. Secs. 3 & 10.

40.00 Set temp. 1/4 Sec. post.

79.44 Intersect N. & S. line, 42 lks. S. of post; from which, I run

S. 89°42'W. on true line.

39.72 Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

79.44 To post Cor. for Secs. 3, 4, 9 & 10.

Land; gently rolling.

Grass good.

Soil; 2nd rate.

N. on random bet. Secs. 3 & 4.

Var. 21°E.

40.00 Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

80.54 Intersect Tp. line, 60 lks. E. of post Cor. for Secs. 3, 4, 33 & 34; from which, I run

S. 26' E. on true line.

40.54 Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

80.54 To post Cor. for Secs. 3, 4, 9 & 10.

Land; broken.

Grass good.

Soil; 2nd rate.