

Subdivisional Lines, T 5 N R 35 E W M.

Chains

W. on true line, course N.89°47'W.

40.22 Set  $\frac{1}{4}$  Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

80.44 To post Cor. for Secs. 20, 21, 28 & 29.

Land; rolling.

Grass good.

Soil; 2nd rate.

N. bet. Secs. 20 & 21.

Var.21°E.

40.00 Set  $\frac{1}{4}$  Sec. post; drove charred stake; dug pits; raised mound, as per instructions.

80.00 Set post Cor. for Secs. 16, 17, 20 & 21. Drove charred stake; dug pits & raised mound, as per instructions.

Land; rolling.

Grass good.

Soil; 2nd rate.

E. on random bet. Secs. 16 & 21.

40.00 Set temp.  $\frac{1}{4}$  Sec. post.

80.40 Intersect N. & S. line, 28 lks. N. of post; from which, I run

N.89°48' W. on true line.

40.20 Set  $\frac{1}{4}$  Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

80.40 To post Cor. for Secs. 16, 17, 20 & 21.

Land; rolling.

Grass good.

Soil; 2nd rate.

N. bet. Secs. 16 & 17.

Var.21°E.

40.00 Set  $\frac{1}{4}$  Sec. post; drove charred stake; dug pits & raised mound, as per instructions.