

Subdivisional Lines, T 5 N R 35 E W M.

Chains

Grass good.
Soil; 2nd rate.
Some timber on Pine Creek, balm, birch & alder.

E. on random bet. Secs. 20 & 29.

- 40.00 Set temp. $\frac{1}{4}$ Sec. post.
79.85 Intersect N. & S. line, 20 lks. N. of post Cor. for Secs.
20, 21, 28 & 29; from which, I run
S.89°51' W. on true line.
39.92 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised
mound, as per instructions.
79.85 To post Cor. for Secs. 19, 20, 29 & 30.
Land; broken.
Grass good.
Soil; 2nd rate.

W. on random bet. Secs. 19 & 30.

- 18.00 Pine Creek, 25 lks. wide, course N.
40.00 Set temp. $\frac{1}{4}$ Sec. post.
79.70 Intersect N. & S. line, 30 lks. N. of post; from which I
run
N.89°47' E. on true line.
39.70 Set $\frac{1}{4}$ Sec. post; dug pits; raised mound, as per instructions.
79.70 To post Cor. for Secs. 19, 20, 29 & 30.
Land; broken.
Grass good.
Soil; 2nd rate.
Some timber on Pine Creek, balm, birch & alder.

N. bet. Secs. 19 & 20.

Var. 21° E.

- 40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised
mound, as per instructions.
80.00 Set post Cor. for Secs. 17, 18, 19 & 20; drove charred