

## Subdivisional Lines, T 5 N R 35 E W M.

Chains	stake; dug pits & raised mound, as per instructions.
30.00	Land; broken. Grass; 2nd rate. Soil; poor 2nd rate.
April 14, 1865.	
	E. on random bet. Secs. 17 & 20.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.10	Intersect N. & S. line, 20 lks. S. of post Cor. for Secs. 16, 17, 20 & 21; from which, I run S.89°57' W.
40.05	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.10	To post Cor. for Secs. 17, 18, 19 & 20. Land; broken. Grass good. Soil; 2nd rate.
	W. on random bet. Secs. 18 & 19.
16.00	Pine Creek, 30 lks. wide, course N.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.60	Intersect N. & S. line, 50 lks. N. of post Cor. for Secs. 18, 19, 13 & 24; from which, I run N.89°39' E. on true line.
39.60	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.60	To post Cor. for Secs. 17, 18, 19 & 20. Land; broken. Grass good. Soil; 2nd rate. Some timber along Pine Creek, balm, birch & alder.
	N. bet. Secs. 17 & 18. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised