

Subdivisional Lines, T 5 N R 36 E W M.

Chains	E. on random bet. Secs. 26 & 35.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect N. & S. line at post; from which I run W. on true line.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
50.00	To summit of hill.
78.00	To foot of hill.
80.00	To post Cor. Land; broken. Grass; good. Soil; 2nd rate.
N. bet. Secs. 26 & 27. Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post on steep hill side, facing ravine on E. Made stone mound; set charred stake, as per instructions.
73.00	To S. Fork of Walla Walla River, course N.W.
80.00	Set post Cor. for Secs. 22, 23, 26 & 27. Drove charred stake and made stone mound, as per instructions. Land; very broken. Soil; good on river bottom. Timber; balm, birch, alder & pine.
E. on random bet. Secs. 23 & 26.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.20	Intersect N. & S. line, 30 lks. S. of post; from which, I run S. 89° 47' W. on true line.
40.10	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.20	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.