

## Subdivistional Lines, T 5 N R 36 E W M.

Chains	N. bet. Secs. 22 & 23.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post, near summit of Divide, bet. N. & S. Forks of Walla Walla River; drove charred stake; made stone mound, as per instructions.
56.07	N. Fork of Walla Walla River, 50 lks. wide, course W.
80.00	To post Cor. for Secs. 14, 15, 22 & 23. Drove charred stake; dug pits; raised mound, as per instructions.
	Land; broken.
	Soil; on bottom, 1st rate.
	Some timber, balm, birch & alder.
	E. on random bet. Secs. 14 & 23.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect N. & S. line, at post; from which, I run W. on true line.
10.00	To S.W. Cor. of field, bearing N. 10 lks.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.00	To post Cor.
	This line passes over spurs of ridges, running to the Walla Walla River.
	Good grass.
	N. bet. Secs. 14 & 15.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits; raised mound, as per instructions.
54.50	To road, course W. of N.
75.00	Crossed road again.
80.00	Set post Cor. for Secs. 10, 11, 14 & 15; drove charred stake; dug pits & raised mound, as per instructions.
	Land; gently rolling.
	Grass; good.
	Soil; 2nd rate.