

Subdivisional Lines, T 5 N R 36 E W M.

Chains	N. on random bet. Secs. 3 & 4.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
81.00	Intersect E. & W. T h eline, 50 lks. W. of post; from which, I run S.22' W. on true line.
40.50	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
81.00	To, post Cor. Land; rolling. Grass; good. Soil; 2nd rate.
	N. bet. Secs. 32 & 33. Var.21°E.
40.00	Set $\frac{1}{4}$ Sec. post on side hill, facing S. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 28, 29, 32 & 33. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Grass; good. Soil; 2nd rate.
	E. on random bet. Secs. 28 & 33.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.09	Intersect N. & S. line, 35 lks. N. of post; from which, I run N.89°45' W. on true line.
40.04	Set $\frac{1}{4}$ Sec. post on hillside, facing W. Drove charred stake; dug pits & raised mound, as per instructions.
80.09	To post Cor. Land; broken. Grass; good. Soil; 2nd rate.
	N. bet. Secs. 28 & 29. Var.21° E.