

Subdivisional Lines, T 5 N R 36 E W M.

Chains	instructions.
	Land; rolling.
	Grass; good.
	Soil; 2nd rate.
<hr/>	
	E. on random bet. Secs. 4 & 9.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.72	Intersect N. & S. line, 32 lks. N. of post; from which, I run N.89°46' W. on true line.
39.86	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.72	To post Cor.
	Land; rolling.
	Grass; good.
	Soil; 2nd rate.
<hr/>	
	N. on random bet. Secs. 4 & 5.
	Var.21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect E. & W. Tp. line; 28 lks. W. of post; from which I run S.12' W. on true line.
40.00	Set $\frac{1}{4}$ Sec. post on level. Drove charred stake; dug pits; raised mound, as per instructions.
80.00	To post Cor.
	Land; gently undulating.
	Grass; good.
	Soil; 2nd rate.
<hr/>	
	N. bet. Secs. 31 & 32.
	Var.21°E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
55.25	Crossed trail, course S.W.
80.00	Set post Cor. for Secs. 29, 30, 31 & 32. Drove charred