

Subdivisional Lines, T 5 N R 36 E W M.

		#
Chains	N. bet. Secs. 17 & 18.	
		Var. 21° E.
2.00	Leave field, course of fence, E.	
3.00	Road, course W.	
5.00	Foot of hill.	
25.00	Summit of hill.	
40.00	Set $\frac{1}{4}$ Sec. post on level. Drove charred stake; dug pits & raised mound, as per instructions.	
80.00	Set post Cor. for Secs. 7, 8, 17 & 18. Drove charred stake; dug pits & raised mound, as per instructions.	
	Land; from summit, gently rolling.	
	Grass; good.	
	Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 8 & 17.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
79.80	Intersect N. & S. line, 15 lks. S. of post; from which I run	
	S. 89° 54' W. on true line.	
14.00	Road, course N.	
39.85	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.	
79.80	To post Cor.	
	Land; rolling.	
	Grass; good.	
	Soil; 2nd rate.	
<hr/>		
	W. on random bet. Secs. 7 & 18.	#
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
79.68	Intersect N. & S. Tp. line, 72 lks. N. of post; from which, I run	
	N. 89° 29' E. on true line.	
39.84	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.	
68.00	Enter river bottom.	