

Subdivisional Lines, T 5 N R 37 E W M.

Chains

12, 13 & 18; from which Cor., I run  
 N.89°41' W. on true line bet. Secs. 12 & 13.

37.40 Enter Meadows

38.00 Creek, 3 lks. wide.

40.20 Set post for  $\frac{1}{4}$  Sec. Cor.; from which  
 A spruce, 10 ins. diam., brs. N.40°E., 27 lks. dist.  
 A " 6 " " " S.20°E., 66 lks. "

41.80 Leave meadows.

42.00 Cross road to meadows.

80.40 The Cor. for Secs. 11, 12, 13 & 14.  
 Land; rolling.  
 Timber; spruce, pine & fir.  
 Two families named Tweeds are settled on little meadow in  
 Sec. 12  
 Soil; No. 1  
 Swamp requires draining. About 3500. above the sea.  
 Oct. 30, 1872.

N. bet. Secs. 11 & 12.

Var. 20°E.

40.00 Set post for  $\frac{1}{4}$  Sec. Cor.; from which  
 A white fir, 10 ins. diam., brs. N.80°W., 11 lks. dist.  
 A " " 4 " " " N.67°E., 14 " "

80.00 Set post for Secs. Cor., 1, 2, 11 & 12; from which  
 A spruce, 30 ins. diam., brs. S.70°E., 30 lks. dist.  
 A " 18 " " " S.37°W., 55. " "  
 A tamarack 20 " " " N.10°W., 25 " "

Land; rolling.  
 Timber; pine, fir & spruce.

E. on random bet. Secs. 1 & 12.

40.00 Set post for temp.  $\frac{1}{4}$  Sec. Cor.

80.35 Intersect E. Bdy. Tp., 41 lks. S. of Cor. for Secs., 1, 6,  
 7 & 12; from this Cor., I run  
 S.89°43' W. on true line.