

## Subdivisional Lines, T 5 N R 37 E W M.

Chains.	N. on random line bet. Secs. 3 & 4. Var. 21°E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.20	Intersect N. Bdy. of Tp., 96 lks. W. from Cor. to Secs. 3, 4, 33 & 34; from this Cor., I run S. 41' W. on true line bet. Secs. 3 & 4.
40.20	Set post for $\frac{1}{4}$ Sec. Cor., mound & pits.
42.00	Bottom of gulch, S.W.
80.20	The Cor. for Secs. 3, 4, 9 & 10. Land; rolling; hills. Good grass. Nov. 6th, 1872.
	N. bet. Secs. 32 & 33. Var. 21 $\frac{1}{2}$ °E.
39.00	Ravine, course W., 200 ft.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., mound & pits.
80.00	Set stone, 13 x 18 x 21, mound & pits, for Cor. to Secs. 28, 29, 32 & 33. Land; mountainous. No timber.
	E. on random line bet. Secs. 28 & 33.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.18	The Cor. for Secs. 27, 28, 33 & 34; from which Cor., I run W. on true line bet. Secs. 28 & 33.
10.00	Summit of rise, falls W.; 400 ft.
40.09	Set post for $\frac{1}{4}$ Sec. Cor.
80.18	The Cor. for Secs. 28, 29, 32 & 33. Land; mountainous. No timber. Good grass.
	N. bet. Secs. 28 & 29. Var. 21 $\frac{1}{2}$ °E.