

## Subdivisional Lines, T 5 N R 37 E W M.

Chains	
	N.89°33' W. on true line bet. Secs. 16 & 21.
39.73	Set post & stone for $\frac{1}{4}$ Sec. Cor.
44.00	Bottom of gulch; ascend.
74.00	Ridge; descend.
79.45	The Cor. for Secs. 16, 17, 20 & 21.
	Land; hilly.
	No timber.
	Good grass.
	N. bet. Secs. 16 & 17.
	Var. 21 $\frac{1}{2}$ ° E.
4.00	Ridge, N.W. 400 ft.; descend.
32.00	Bottom of ravine; ascend.
40.00	Set stone, 8 x 16 x 16, for $\frac{1}{4}$ Sec. Cor.
80.00	Set stone, 10 x 15 x 28, for Cor. to Secs. 8, 9, 16 & 17.
	Mountainous land.
	Good grass.
	Nov. 7, 1872.
	E. on random line bet. Secs. 9 & 16.
40.00	Set stump for temp. $\frac{1}{4}$ Sec. Cor.
80.32	Intersect N. & S. line, 24 lks. N. of Cor. for Secs. 9, 10, 15 & 16; from this Cor., I run
	N.89°50' W. on true line bet. Secs. 9 & 16.
25.32	Ridge falls W.
40.16	Set post & marked stump for $\frac{1}{4}$ Sec. Cor.
48.00	Cross ravine; descend.
66.00	Cross ridge, falls N.80°W.
80.32	Cor. for Secs. 8, 9, 16 & 17.
	Land; hilly.
	Good grass.
	N. bet. Secs. 8 & 9.
	Var. 21° E.
9.75	Cross road to timber.
10.00	Summit of ridge, 600 ft. falls W.