

## Subdivisional Lines, T 5 N R 37 E W M.

Chains	N. bet. Secs. 19 & 20.	Var. 21° E.
	Ascend.	
40.00	Set post & stone for $\frac{1}{4}$ Sec. Cor.	
56.00	Ridge falls W.; descend 400 ft.	
80.00	Set stone, 9 x 12 x 20 for Cor. to Secs. 17, 18, 19 & 20. Land; hilly. Good grass.	
	E. on random line bet. Secs. 17 & 20.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.10	Intersect N. & S. line, 80 lks. S. of Cor. for Secs. 16, 17, 20 & 21; from which Cor., I run S. 89° 47' W. on true line bet. Secs. 17 & 20.	
40.05	Set post for $\frac{1}{4}$ Sec. Cor.	
64.10	Spr. branch, 1 lk. wide.	
80.10	The Cor. for Secs. 17, 18, 19 & 20. Land; hilly. Good grass.	
	W. on random line bet. Secs. 18 & 19.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.28	Intersect W. Bdy. of Tp., 18 lks. N. of Cor. for Secs. 13, 18, 19 & 24; from this Cor., I run N. 89° 52' E. on true line bet. Secs. 18 & 19.	
29.00	Spr. branch, 4 lks. wide, S.W.	
40.28	Set post & stone, for $\frac{1}{4}$ Sec. Cor.; ascend.	
80.28	The Cor. for Secs. 17, 18, 19 & 20. Land; hill. Good grass.	
		Dec. 16th, 1872.
	N. bet. Secs. 17 & 18.	Var. 21° E.
22.00	Spr. branch, 7 lks. wide, W.; ascend.	