

## Subdivisional Lines, T 5 N R 37 E W M.

|        |                                                                                                                                              |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------|
| Chains | N. on random line bet. Secs. 5 & 6.                                                                                                          |
| 40.00  | Set post for temp. $\frac{1}{4}$ Sec. Cor.                                                                                                   |
| 80.28  | Intersect N. Bdy. of Tp., 64 lks. W. from Cor. for Secs.<br>5, 6, 31 & 32; from which Cor., I run<br>S.27' W. on true line bet. Secs. 5 & 6. |
| 17.28  | Bottom of ravine, 300 ft. W.                                                                                                                 |
| 40.28  | Set stone, 8 x 10 x 13, for $\frac{1}{4}$ Sec. Cor.                                                                                          |
| 70.28  | Ascend hill.                                                                                                                                 |
| 80.28  | The Cor. for Secs. 5, 6, 7 & 8.<br>Land; hilly.<br>Good grass.<br>Soil; 2nd rate.                                                            |
|        | Completed Dec. 18th 1872.                                                                                                                    |

---

General Description.

This Tp. is much broken. The eastern portion timbered with pine, fir, tamarack, spruce, birch, alder & willow are the principle. A small swamp in Secs. 1 & 12. The western portion is more adapted to agriculture; there being some good land; though much broken it is settling up fast.

Completed Dec. 18, 1872.

South Bdy. T 6 N R 37 E W M.,  
As surveyed by Odell & Lewis, U.S. Deputy Surveyors,  
Under Contract No. 110, Joint Contract,  
Dated Feby. 7, 1865.

E. on S. Bdy. of Secs. 31, T 6 N R 37 E

Var. 21° E.

|       |                                                                                                                                                                                         |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 19.00 | Ploughed land.                                                                                                                                                                          |
| 25.00 | Leave ploughed land.                                                                                                                                                                    |
| 40.00 | Set $\frac{1}{4}$ Sec. Cor. stone, 16 x 12 x 4, basalt.                                                                                                                                 |
| 80.00 | Set post Cor. for Secs. 31, 32, 5 & 6, on hillside, facing<br>W.; deposited marked stone; dug pits & raised mound, as<br>per instructions.<br>Land; broken. Good grass. Soil; 1st rate. |