

Exterior Lines, T 5 N R 38 E W M.

Chains W. 40 chs., hilly. E. 40 chs., table.
Good timber; fir, spruce, tamarack & pine.

E. on S. Bdy. of Sec. 33.

Var. 23°E.

- 23.00 Leave table. Descend & leave timber.
- 40.00 Set basalt stone, 20 x 18 x 12, for $\frac{1}{4}$ Sec. Cor., on side hill, facing N.E.
- 51.00 Gulch, 350 ft. falls N.W. Ascend.
- 80.00 Set post for Cor. to Secs. 3, 4, 33 & 34, from which
- A pine, 12 ins. diam., brs. N. 20°E., 29 lks. dist.
 - A " 18 " " " N. 37°W., 42 " "
 - A " 27 " " " S. 42°E., 71 " "
 - A tamarack, 15 ins. diam., brs. S. 34°W., 91 lks. dist.

Land; hilly, 2nd rate.

Timber; pine, fir, tamarack, spruce & willow.

Sept. 30th, 1872.

E. on S. Bdy. of Sec. 34.

Var. 23°E.

- 39.00 Summit of ridge, 60 ft.
- 40.00 Set basalt stone, 20 x 18 x 10 ins. in mound of stone, for $\frac{1}{4}$ Sec. Cor., on side hill, face E.
- 64.90 Spring branch, 1 lks. wide, falls N.W.
- 66.90 Spring branch, 2 lks. wide, falls N.W.
- 80.00 Set post for Sec. Cor. 2, 3, 34 & 35, from which
- A white fir, 5 ins. diam., brs. S. 50°W., 10 lks. dist.
 - A " " 6 " " " N. 8°E., 20 " "
 - A red " 12 " " " N. 27°W., 45 " "

Land; hilly.

Timber; tamarack, fir & spruce.

E. on S. Bdy. of Secs. 35.

Var. 21 $\frac{1}{2}$ °E.

- 4.70 Summit of ridge, 300 ft.