

## Exterior Lines, T 5 N R 39 E W M.

Chains	
17.90	Leave opening and enter timber, brs. E. & W., 300 ft. above ravine and top of ridge brs. E. & W. and Descend.
40.00	Set alder post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., 1000 ft. below top of ridge, marked $\frac{1}{4}$ S on W. face; from which An alder, 4 ins. diam., brs. S. 35° E., 11 lks. dist., marked $\frac{1}{4}$ S B T. An alder, 5 ins. diam., brs. S. 55° W., 19 lks. dist., marked $\frac{1}{4}$ S B T.
40.75	Spring branch, 7 lks. wide, runs N.W., 50 ft. below $\frac{1}{4}$ Sec. Cor. and Ascend.
45.00	Top of ridge brs. E. & W., 100 ft. above spring branch.
50.85	Ravine, course W., 100 ft. below top of ridge. Aug. 9th, 1882.
54.00	Spring branch, 5 lks. wide runs SW., 100 ft. below last ravine. Ascend 1000 ft. to
75.50	Dry ravine, course S. E
90.08	Intersect S. Bdy. of Tp. 6 N R 38 E., 18.22 chs. E. of Cor. to Secs. 35 & 36, 1 & 2, which is a post, 4 ins. sq., in stone mound. Post, marked T 6 N R 38 E S 36 on N.E., S. 35 on N.W. and S 2 on S.W. & T 5 N S 1 on S.E. faces, with 5 notches on W. and 1 on E. edges; from which A spruce, 10 ins. diam., brs. N. 2° E., 49 lks. dist., marked S 36 B T., remark the tree, T 6 N R 38 E S 36 B T., and obliterate marks on post pertaining to Secs. S. of line and mark a spruce, 8 ins. diam., brs. N. 71° W., 107 lks. dist., marked T 6 N R 38 E S 35 B T., and at the point, 18.22 chs. E. of this Cor.
	Set post, $4\frac{1}{2}$ ft. long, 4 ins. sq., 24 ins. in ground, for Closing Cor. to Tp. 5 N. Rs. 38 & 39 E., marked T 5 N