

Subdivisional Lines Secs. 5, 6, 7 & 8, T 5 N R 38 E W M.

Chains

W. on random line bet. Secs. 6 & 7.

40.00 Set post for temp. $\frac{1}{4}$ Sec. Cor.

79.82 Intersect W. Bdy. of Tp., 34 lks. N. of Cor. for Secs. 1, 6, 7 & 12; from which, I run
N.89°45'E. on true line bet. Secs. 6 & 7.

9.32 J. Cassel's house N., 3 chs. dist.

10.50 Enter small prairie.

39.82 Set post for $\frac{1}{4}$ Sec. Cor.; from which
A tamarack, 18 ins. diam., brs. S.15°E., 37 lks. dist.

64.82 Leave burnt woods.

79.82 The Cor. for Secs. 5, 6, 7 & 8.
Land; rolling, 1st rate.

N. on random line bet. Secs. 5 & 6. Var. 20°E.

40.00 Set post for temp. $\frac{1}{4}$ Sec. Cor.

80.47 Intersect N. Bdy. of Tp., 165 lks. W. from Cor. for Secs. 5, 6, 31 & 32; from which Cor., I run
S.1°11'W. on true line bet. Secs. 5 & 6.

33.47 Leave timber.

40.47 Set post for $\frac{1}{4}$ Sec. Cor.; from which
A tamarack, 12 ins. diam., brs. N.85°W., 89 lks. dist.
A spruce, 13 ins. diam., brs. N.80°E., 40 lks. dist.

55.00 Leave burnt woods.

65.00 Top of ridge.

80.47 The Cor. for Secs. 5, 6, 7 & 8.
Land; rolling.
Soil; good.
Timber; pine, fir, tamarack & spruce, alder & willow.
Oct. 27th, 1872.

General Description.

These four Secs. are the only ones of any value in the Tp. There is about 40 acres of swamp prairie in Sec. 8, about 80 acres in Sec. 7. The timber surrounding is excellent pine, fir, tamarack, spruce & willow.