

Subdivisional Lines, T 5 N R 38 E W M.

| Chains |  |
|--------|--|
| 34.50  | Head of ravine, S.E.<br>Steep, bluffy ascent.  |
| 38.50  | Opening 2 chs. wide.   |
| 40.00  | A point, 400 ft. above the Sec. Cor. and<br>Set basalt stone, 15 x 10 x 10 ins., 6 ins. in ground,<br>( strike rock and place mound of stone firmly about<br>Cor.), for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; from<br>which<br>A fir, 14 ins. diam., brs. S.53 $\frac{1}{2}$ °W., 88 lks. dist.,<br>marked $\frac{1}{4}$ S @ B T.<br>A fir, 17 ins. diam., brs. N.19°E., 53 lks. dist.,<br>marked $\frac{1}{4}$ S 4 B T. |
| 40.75  | Leave timber and cross S. edge of opening N.W.   |
| 44.50  | Enter timber, brs. N. & S.   |
| 46.25  | Stock trail, brs. N.70°E. and S.70°W.  |
| 47.25  | Top of rise on main divide bet. Mill Creek and Walla Walla<br>River, brs. N.E. & S.W.  |
| 50.00  | Trail from settlements to Grand Ronde, brs. N.E. & S.W.<br>Thence through heavy timber and scanty undergrowth.<br>Descending gradually.  |
| 52.23  | A tamarack, 18 ins. diam., on line, I mark with 2 notches<br>on E. & W. sides.   |
| 59.50  | Trail, brs. N.60°E. & S.60°W.<br>Branch of main trail.   |
| 69.70  | Foot of descent.<br>Stream, 4 lks. wide, runs N W.   |
| 70.15  | Stock trail, brs. N.W. & S.E.<br>Gradual slope.  |
| 75.00  | Enter partially burnt timber.  |
| 78.00  | Heavy timber.  |
| 81.27  | A point, 300 ft. above $\frac{1}{4}$ Sec. Cor. and<br>Intersect N. & S. line, E. Bdy. of Secs. 8, 9 chs., 23 lks.<br>S. of Cor. of Secs. 4, 5, 8 & 9, which is described by<br>the Surveyor-General, as a post; from which<br>A white fir, 24 ins. diam., brs. N.15°W., 25 lks.<br>dist., marks not stated.  |