

Subdivisional Lines, T 5 N R 38 E W M.

Chains

45.00 Top of rise.
 Descend.

47.50 Steep descent.
 Hill brs. N.E. & S.

61.00 Foot.
 Stream, 5 lks. wide, runs N.40°E.
 Ascend steep hill, brs. N.E. & S.W.

73.25 Top of point, brs. N.15°W.
 Descend.

78.52 A point, 400 ft. below $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs.
 29, 30, 31 & 32.
 Land; mountainous.
 Soil; gravelly loam & stone, 2nd, 3rd & 4th rates.
 Timber; fir, tamarack, pine & spruce.
 Undergrowth; fir, tamarack, spruce, pine, alder, willow,
 huckleberry, fern and bunch grass.
 Mountainous land; 78.52 chs.

August 3, 1899.

August 7:

N.0°5' W. bet. Secs. 29 & 30.
 Descending through heavy timber
 Hill brs. N.50°E. & S.50°W.

6.50 Hill brs. N.10°E. & S.10°W.

22.50 Leave timber, brs. N.E. & S.W.
 Hill, N. & S.

32.25 Rocky spur, brs. N.30°E.
 Steeper descent along N.W. slope of spur.

35.42 A fir, 18 ins. diam., on line, I mark with 2 notches on N.
 and S. sides.
 Enter timber, brs. N.20°E. & S.20°W.

40.00 A point, 1600 ft. below Sec. Cor. and
 Set basalt stone, 18 x 10 x 6 ins., 13 $\frac{1}{2}$ ins. in ground, for
 $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{2}$ on W. face; from which
 A fir, 8 ins. diam., brs. N.83°E., 52 lks. dist.,