

Dependent Resurvey of S. Rdy., Sec. 36, T 6 N R 38 E W M.

Chains	
	dense undergrowth.
1.70	Ravine, course N., asc. 247 ft. over NE. slope.
15.38	(Point 40.00 chs. in westing from the Cor. of Secs. 5, 6, 31 & 32.) Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{4}$ Sec. Cor. of Sec. 6 only, with brass cap, marked
	$\frac{1}{4}$ S 6 1932
	from which
	A fir, 18 ins. diam., brs. S.47°E., 35 lks. dist., marked $\frac{1}{4}$ S 6 B T.
	A fir, 12 ins. diam., brs. S.20°W., 86 lks. dist., marked $\frac{1}{4}$ S 6 B T.
17.30	Flat topped ridge, brs. NW. & SE.; desc. 103 ft. over gradual SW. slope.
40.57	Proportionate point for $\frac{1}{4}$ Sec. Cor. of Secs. 36 only. Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{4}$ Sec. Cor. of Sec. 36 only, with brass cap, marked
	$\frac{1}{4}$ S 36 1932
	from which
	A fir, 16 ins. diam., brs. N.43°E., 33 lks. dist., marked $\frac{1}{4}$ S 36 B T.
	A spruce, 12 ins. diam., brs. N.22°W., 55 lks. dist., marked $\frac{1}{4}$ S 36 B T.
	Continue to desc. 52 ft. over SW. slope.
42.87	Road, Walla Walla to Skyline, brs. NW. & SE.
45.00	Head of ravine, course S.20°W.; asc. 90 ft. over SE.
49.10	Road, Walla Walla to Skyline, brs. NE. & SW.
55.39	(Point 80.00 chs. in westing from the Cor. of Secs. 5, 6, 31 & 32.) Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for Cor. of lots 4 & 5, with brass cap, marked
	$\frac{5}{4}$ S 6 1932
	from which
	A tamarack, 30 ins. diam., brs. S.42 $\frac{1}{2}$ °E., 36 lks. dist., marked L 4 S 6 B T.
	A fir, 12 ins. diam., brs. S.36°W., 51 lks. dist., marked L 5 S 6 B T.