

Subdivision of T. 4 N., R. 39 E.

Chains	Feet
	<p>A fir, 20 ins. diam., bears S. 14° E., 36 lks. dist. marked T 5 N R 39 E S 18 C C B T.</p> <p>From this point the cor. of secs. 12 & 13 only, bears S. 0°27' E., 8.41 chs. dist., heretofore described.</p> <p>Land; mountainous. Soil; sandy loam, rocky, 3rd rate. Timber; fir, pine, spruce and tamarack. Undergrowth, alder, vinemaple, salal, huckleberry, fern, laurel, elder, syringa, buck brush and thorn.</p> <hr/> <p>To complete the survey of sec. 18, I go to the $\frac{1}{4}$ sec. cor. of sec. 13 only, on E. bdy. of T. 5 N., R. 38 E., and run</p> <p>N. 0°20' E., along the E. bdy. of sec. 13.</p>
8.35	<p>Midpoint on the W. bdy. of sec. 18.</p> <p>Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{4}$ sec. cor. of sec. 18 only, with brass cap marked</p> <div style="text-align: center;"> $\frac{1}{4}$ S 18 1935 </div> <p style="text-align: right;">from which</p> <p>A fir, 20 ins. diam., brs. N. 62° E., 357 lks. dist., marked $\frac{1}{4}$ S 18 B T</p> <p>A fir, 52 ins. diam., brs. S. 12° E., 45 lks. dist., marked $\frac{1}{4}$ S 18 B T</p> <hr/> <p>From the cor. of secs. 7, 8, 17 & 18.</p> <p>N. 0° 05' W., bet. secs. 7 & 8</p> <p>Desc. 10 ft. over NW. slope, through heavy second growth timber and dense undergrowth.</p>
0.10	<p>Ravine, course N. 80° W.; asc. 210 ft. over SW. slope.</p>
7.25	<p>Spur, slopes W.; desc. 447 ft. over broken NW. slope.</p>
27.15	<p>South Fork of the Walla Walla River, 15 lks. wide, course S. 20° W.; from N., thence in river.</p>
29.40	<p>Leave S. Fork of the Walla Walla River, 15 lks. wide, course S., from NE.; asc. 350 ft. over SE. slope.</p>
33.30	<p>S. Fork of the Walla Walla River Trail, bears NE. and SW.</p>
40.00	<p>Set an iron post, 3 ft. long, 1 in. diam., 20 ins. in the ground to solid rock and in a mound of stone to top, for $\frac{1}{4}$ Sec. cor., with brass cap marked</p> <div style="text-align: center;"> $\frac{1}{4}$ S 7 S 8 1935 </div> <p style="text-align: right;">from which</p>