

Exterior Lines of T. 5 S., R. 31 E., W.M.

Chains		Feet
40.00	Set basalt stone 20 x 14 x 8 on slight N.W. slope for $\frac{1}{4}$ Sec. Cor. A Pine 22 ins. diam. brs. E. 68 lks. dist. A Pine 36 ins. diam. brs. S. 48° W. 58 lks. dist.	
80.00	Set basalt stone 18 x 16 x 8 on level for Cor. to Secs. 30, 31, 25 and 36. A Pine 18 ins. diam. brs. N. 77° E. 46 lks. dist. A Pine 10 ins. diam. brs. S. 60° E. 103 lks. dist. A Pine 16 ins. diam. brs. N. 66° W. 34 lks. dist. No tree near on S.W. Land; surface steep bluff on S. 23 Chs., N. 57 Chs. undulating, Soil; 3rd and 2nd rate and somewhat stoney. Some good farming land on N. $\frac{1}{2}$ mile, N. 57 Chs. mostly heavy timber with some open glade, Pine, Tamarack and Fir. Good grass.	
33.50	N. on the W. Bdy. of Sec. 30, Var. 19° 45' E. A Ravine, course N.E.	
40.00	Set basalt stone 14 x 10 x 8 on S.E. slope for $\frac{1}{4}$ Sec. Cor. A Pine 16 ins. diam. brs. S. 12° E. 94 lks. dist. A Pine 22 ins. diam. brs. N. 85° W. 43 lks. dist.	
80.00	Set basalt stone 17 x 10 x 7 on S.E. slope for Cors. to Sec. 19, 30, 24 and 25. A Fir 10 ins. diam. brs. N. 47° E. 31 lks. dist. A " 12 " " " S. 42 E. 38 " " A " 8 " " " S. 40 W. 23 " " A " 20 " " " N. 13 W. 88 " " Land; surface rolling and general, slopes Eastward. Soil; 2nd and 3rd rate. Mostly heavy timber with open glades, Pine, Tamarack and Fir. Mostly good grass. A large part is good farming land.	
	N. on the W. Bdy of Sec. 19,	