

Exterior Lines of T. 5 S., R. 29 E., W.M.

Chains		Feet
	Soil; 2nd and 3rd rate, heavily timbered with Pine, Tamarack and fir timber, and some underbrush of Pine, Fir, and Tamarack. Some open glades.	
	N. bet. Secs. 12 and 7,	
		Var. 20° 45' E.
	Ascending,	
40.00	Set a basalt stone 16 x 10 x 5 ins. 11 ins. in ground on level in open glade for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, A Pine 20 ins. diam. brs. N. 48° E. 155 lks. dist. marked $\frac{1}{4}$ S.B.T.	
	No tree on W. side.	
80.00	A Tamarack, 6 ins. diam. on level for Cor. to Secs. 1, 12, 6 and 7, marked, T. 5 S., S. 6 on N.E. R. 30 E. S. 7 on S.E. T. 5 S., S. 12 on S.W. R. 29 E., S. 1 on N.W., faces, from which, A Fir 6 ins. diam. brs. N. 42° E. 20 lks. dist. marked T. 5 S., R. 30 E., S. 6 B.T. A Fir 8 ins. diam. brs. S. 22° E. 58 lks. dist. marked T. 5 S. R. 30 E., S. 7 B.T. A Pine 6 ins. diam. brs. S. 36° W. 25 lks. dist. marked T. 5 S., R. 29 E. S. 12 B.T. A Tamarack 18 ins. diam. brs. N. 56° W. 40 lks. dist. marked T. 5 S., R. 29 E. S. 1 B.T.	
	Land; surface rolling,	
	Soil; 3rd and 2nd rate, about 2/3 of this mile is heavily timbered with Pine, Tamarack and Fir. Some undergrowth of Pine, Fir and Tamarack. Some open glades.	
	N. bet. Secs. 1 and 6,	
		Var. 20° E.