

Exterior Lines, T.5 S., R.31 E., W. M.

Chains	N. on E. Bdy. of Secs. 12.	Var. 19°15'E.
32.50	Brook, 30 lks. wide, course W.	
40.00	Set basalt stone, 18 x 10 x 8, in mound of stone, on level. prairie, for $\frac{1}{4}$ Sec. Cor.	
43.00	Leave bottom prairie.	
45.00	On bench table land	
78.00	Enter timber, E. & W.	
80.00	Set pine post, in level, for Cor. to Secs. 1, 12, 6 & 7. A pine, 30 ins. diam., brs. N.76°E., 55 lks. dist. A " 8 " " " S.40°E., 22 " " A " 8 " " " S.26°W., 42 " " A " 44 " " " N.63°W., 140 " "	
	Land; surface mostly level. Soil; 1st & 2nd rate. Good grass. Some scattering pine timber on N. $\frac{1}{2}$ mile. Excellent farming land.	
	N. on E. Bdy. of Sec. 1.	Var. 19°45'E.
6.00	Leave timber, course E. & W.	
40.00	Set basalt stone, 12 x 10 x 5, on level, in mound of stone, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set pine post, 5 ft. long, 6 ins. sq., on slight slope and dug pits & raised mound of earth, for Cor. to Tps. 4 & 5 S., Rs. 31 & 32 E., W. M. A pine, 12 ins. diam., brs. N.77°W., 235 lks. dist. No other trees near.	
	Land; surface a nearly level. Soil; 1st rate. Excellent grass, & farming land.	
		Oct. 2, 1880.
	Subdivisional Lines, T.5 S., R.31 E., W. M. As surveyed by Geo. S. Pershin, Under the same Contract & Date.	
	N. bet. Secs. 35 & 36.	Var. 19°E.
40.00	Set basalt stone, 14 x 12 x 5, on slight N. slope, in	