

Subdivisional Lines, T.5 S., R.31 E., W. M.

Chains	E. on random lien ber. Secs. 3 & 10. Var. 19°15'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.96	Intersected N. & S. line, at Cor. to Secs. 2, 3, 10 & 11, from which Cor., I run W. on true line bet. Secs. 3 & 10. Var. 19°45'E.
18.00	Snipe creek, course S., 20 lks. wide.
39.98	Drove post, 4 ins. sq., 4 ft. long, in soft ground, for $\frac{1}{4}$ Sec. Cor.
79.96	The Cor. to Secs. 3, 4, 9 & 10. Land; surface slightly undulating. Soil; 1st & 2nd rate. Good grass, excellent farming land.
	N. on random line bet. Secs. 3 & 4. Var. 19°15'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.80	Intersected N. Bdy., 62 lks. E. of Cor. to Secs. 3 & 4, from which Cor., I run S. 00°27'E. on true line bet. Secs. 3 & 4. Var. 20°45'E.
39.80	Set fir post; dug pits & raised mound of earth, for $\frac{1}{4}$ Sec. Cor. Gilliland's house brs. S. 64°E.
52.00	Spring branch, course N.E. Gilliland's house brs. N. 80°E.
79.80	The Cor. to Secs. 3, 4, 9 & 10. Land; surface undulating. Soil; 1st rate. Good grass. Good natural meadow, excellent farming land. Oct. 8, 1880.
	N. bet. Secs. 32 & 33. Var. 21°00'E.
.50	Leave creek, course S.W.
22.00	On spur, extends East,
34.50	Camas Creek, 60 lks. wide, course S.E.