

Subdivisional Lines, T.5 S., R.31 E., W. M.

Chains	
	Soil; 2nd & 3rd rate. Good grass. Some scattering pine timber, some good farming land.
	E. on random line bet. Secs. 4 & 9. Var. 19°45'E.
40.00	Set stake for temp. $\frac{1}{4}$ Sec. Cor.
80.38	Intersected N. & S. line, at Cor. to Secs. 3, 4, 9 & 10 from which Cor., I run W. on true line bet. Secs. 4 & 9. Var. 19°15'E.
40.19	Set basalt stone, 16 x 10 x 7, on S.E. slope, for $\frac{1}{4}$ Sec. Cor. in mound of stone. A pine, 20 ins. diam., brs. N. 16°W., 265 lks. dist., No tree S. Caldwell's house is about due N. about 10 chs., but cannot be seen from line.
80.38	The Cor. to Secs. 4, 5, 8 & 9. Land; surface, undulating. Soil; 1st & 2nd rate. Scattering pine timber on W. $\frac{1}{2}$ mile. Good grass. Large part good farming land.
	N. on random line bet. Secs. 4 & 5. Var. 19°45'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.12	Intersected N. Bdy. , 18 lks. E. of Cor. to Secs. 4 & 5, from which Cor., I run S. 00°08' E. on true line bet. Secs. 4 & 5. Var. 20°00'E.
6.00	A ravine, course E.
40.12	Set basalt stone, 18 x 12 x 5, in mound of stone, for $\frac{1}{4}$ Sec. Cor., on level.
80.12	The Cor. to Secs. 4, 5, 8 & 9. Land; surface undulating. Soil; 3rd & 2nd rate. Good grass. No timber. Adapted to