

Subdivisional Lines, T.5 S., R.31 E., W. M.

Chains	Heavy timber, pine, tamarack & fir, with glades. Some grass
	W. on random line bet. Secs. 18 & 19. Var. 24°00'E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.55	Intersected W. Bdy., 52 lks. S. of Cor. to Secs. 18 & 19, from which Cor., I run S.89°38' E. on true line bet. Secs. 18 & 19. Var. 19° 45'E.
39.55	Set basalt stone, 18 x 12 x 5, on S. slope, for $\frac{1}{4}$ Sec. Cor. A pine, 24 ins. diam., brs. N.82°W., 112 lks. dist. A pine, 5 ins. diam., brs. S.28°W., 85 lks. dist.
77.50	In ravine, course W.
79.55	The Cor. to Secs. 17, 18, 19 & 20. Land; surface rolling. Soil; 2nd & 3rd rate. Heavy timber, with open glades, pine, tamarack & fir, with some young fir & tamarack underbrush, some grass.
	N. bet. Secs. 17 & 18. Var. 24°00'E.
6.00	Ravine, course N.E.
40.00	Set basalt stone, 15 x 10 x 8 ins open glade on S.E. slope for $\frac{1}{4}$ Sec. Cor. A pine, 30 ins. diam., brs. S.84°W., 187 lks. dist. No tree E.
71.00	Leave timber, course E. & W.
80.00	Set basalt stone, 20 x 10 x 6 & post, in mound of stone, on E. slope, for Cor. to Secs. 7, 8, 17 & 18. Land; surface rolling. Soil; 3rd rate. Scattering pine & fir timber; good grass. Oct. 15, 1880.
	E. on random line bet. Secs. 8 & 17. Var. 20°30'E.