

S. Bdy. of T. 5 S., R. 32 E., W.M.

Chains

Feet

A Tamarack, 14 ins. diam. brs. N. 40° W., 79 lks. dist.

A " 24 " " " N. 46° E., 30 lks. dist.

Land; surface N. mountain side.

Soil; 2nd rate, heavy timber, Tamarack, Pine and Fir;
dense young timber, underbrush, good farming land if
cleared.

E. on a true line along the S. Bdy. of Sec. 36

Var. 18° 15' E.

Along N. side, near foot of ridge

39.90 A Brook, 5 lks. wide, course N.

40.00 Set basalt stone, 20 x 14 x 6, on E. bank of brook, for
¼ Sec. Cor.

A Fir, 18 ins. diam. brs. N. 48° E., 14 lks. dist.

A Spruce, 10 ins. diam. brs. S. 62° W., 30 lks. dist.

72.00 On level

80.00 Set Pine post, 6 ins. sq. on two sides, on level for Cor.
to Tps. 5 S., Rs. 32 & 33 E.

A Pine, 18 ins. diam. brs. N. 21° W., 16 lks. dist.

A Pine, 8 ins. diam. brs. N. 73° E., 110 lks. dist.

Land; surface N. slope of ridge.

Soil; 2nd and 1st rate, heavy timber, scattering on E.

20 Chs., Tamarack, Pine and Fir. Some grass on E. 20

Chs. Some good farming land.

Sept. 9, 1880

Exterior Bdy. of T. 5 S., R. 32 E., W.M.
As surveyed by, George S. Pershin, U.S. Deputy Surveyor,
Under Contract No. 390,
Dated May 12, 1881.

I begin at the Cor. to Tp. 5 S., Rs. 32 and 33 E., on the
1st Standar Paralled S. of Base Line. The monument
is in good repair.

A post properly marked and witness tree standing,

A Pine, 8 ins. diam. brs. N. 72° E., 11 lks. dist.

A Pine 18 ins. diam. brs. N. 20° W., 16 lks. dist.

And with Buts improved Solar Compass (Young of Philadelphia