

Subdivisional Lines of T. 5 S., R. 32 E. W.M.

Chains		Feet
	Soil; excellent 2nd rate, some 1st rate. Heavy timber on S. 48 Chs. Pine, Tamarack and Fir, thick underbrush. Good grass in open prairie.	
	<hr/>	
	E. on a random line bet. Sec. 25 & 26	
		Var. 21° 00' E.
40.00	Set post for Temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersected E. Bdy at cor. to Secs. 25 and 36, from which Cor. I run,	
	W. on a true line bet. Secs. 25 & 26	
		Var. 16° 05' E.
.50	Top of creek, bluff, course N. and S.	
.00	Leave timber	
40.20	Set basalt stone, 18 x 12 x 5, in mound of stone on slight N.W. slope for $\frac{1}{4}$ Sec. Cor.	
80.40	The Cor. to Secs. 25, 26, 35 and 36.	
	Land; surface undulating,	
	Soil; 2nd and 3rd rate, excellent grass. Some good farming land, about $\frac{1}{2}$ of Sec. 36 is good farming land.	
	<hr/>	
	N. bet. Sec. 25 and 26	
		Var. 21° 00' E.
40.00	Set basalt stone, 14 x 12 x 7 in mound of stone on slight N.W. slope for $\frac{1}{4}$ Sec. Cor.	
80.00	Set basalt ston, 24 x 12 x 6, and post in mound of stone on slight N.W. slope for Cor. to Secs. 23, 24, 25 & 26.	
	Land; surface undulating	
	Soil; 2nd and 3rd rate, excellent grass. Larger part, good farming land.	
	<hr/>	
	E. on a random line bet. Sec. 24 & 25.	
		Var. 21° 30' E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.08	Intersected E. Bdy., 24 lks. N. of Cor. to Sec. 24 & 25, from which Cor. I run,	
	N. 89° 50' W. on a true line between Sec. 24 & 25.	