

Subdivisional Lines of T. 5 S., R. 32 E., W.M.

Chains		Feet
	Var. 19° 15' E.	
40.00	Set basalt stone, 28 x 14 x 8, on rocky N.W. slope for ¼ Sec. Cor.	
63.00	Enter timber, course E. and W.	
80.00	Set basalt stone, 20 x 10 x 5 on slight N.W. slope for Cor. to Sec. 14, 15, 22 & 23.	
	A Pine, 18 ins. diam. brs. N. 56° E., 109 lks. dist.	
	A " 10 " " " S. 48° E., 111 " "	
	A " 10 " " " S. 66° W., 165 " "	
	A " 16 " " " N. 76° W., 75 " "	
	Land; surface undulating	
	Soil; 2nd and part 1st rate. good grass. Some Pine timber on N. 17 Chs., greater part good farming land.	
<hr/>		
	E. on a random line bet. Sec. 14 & 23	
	Var. 18° 30' E.	
40.00	Set post for temp. ¼ Sec. Cor.	
79.94	Intersected N. and S. line, 28 lks. S of Cor. to Secs. 13, 14, 23 & 24, from which Cor. I run S. 89° 48' W. on a true line bet. Secs. 14 & 23.	
38.00	Enter timber, course N.W. and S.E., steep descent	
39.97	Set basalt stone, 16 x 14 x 4 on W. face of creek bluff for ¼ Sec. Cor.	
	A Pine 42 ins. diam. brs. N. 41° W., 118 lks. dist.	
	A Pine, 16 ins. diam. brs. S. 76° E., 58 lks. dist.	
44.00	Cable creek, 50 lks. wide, course N.W.	
79.94	The Cor. to Sec. 14, 15, 22 & 23	
	Land; surface W. 42 Chs. broken	
	Soil; 3rd, 2nd & small part 1st rate, heavy Pine, Tamarack & Fir timber on W. 42 Chs. good grass on prairie. Some good farming land.	
<hr/>		
	N. bet. Sec. 14 & 15	
	Var. 18° 30' E.	
36.50	Cable creek, 40 lks. wide, course N.W.	