

First Standard Parallel South,
S. Bdy., T.5 S., R.33 E., W. M.
As surveyed by Geo. S. Pershin,
Under Contract No. 362,
Dated Aug. 2, 1880.

Chains	
	E. on true line along S. Bdy. of Sec. 31. Var. 18°45'E.
36.00	Begin descent to deep canyon.
40.00	Set pine post, on E. Face of bluff, for $\frac{1}{4}$ Sec. Cor. A fir, 6 ins. diam., brs. N.28°W., 5 lks. dist. A fir, 14 ins. diam., brs. S.12°W., 23 lks. dist.
57.00	Spring branch, course N.E.
73.50	Brook, 25 lks. wide, course N.W.
80.00	Set basalt stone, 24 x 14 x 8, on S. face of bluff, for Cor. to Secs. 31 & 32. A pine, 40 ins. diam., brs. N.67°W., 39 lks. dist. A pine, 6 ins. diam., brs. N.46°E., 19 lks. dist. Land; surface, W.36 chs., nearly level- E.44 chs., very broken. Soil; 2nd, 3rd & 1st rate. Heavy timber on E.44 chs.- W.36 chs., scattering. Fir, tamarack & pine. Some good farming land.
	E. on true line along S. Bdy. of Secs. 32. Var. 19°00'E.
18.00	On spur, extending S. Across spurs & small ravines.
40.00	Set pine post, in small open glade, in mound of stone, for $\frac{1}{4}$ Sec. Cor. A pine, 24 ins. diam., brs. N.72°W., 92 lks. dist. A pine, 22 ins. diam., brs. S.84°W., 99 lks. dist.
80.00	Set pine post, in mound of stone, on S. face of spur, for Cor. to Secs. 32 & 33. A pine, 12 ins. diam., brs. N.17°W., 70 lks. dist. A pine, 10 ins. diam., brs. N.70°E., 32 lks. dist. Land; surface very broken. Soil; 2nd & 3rd rate. Mostly heavy timber, with open glades, pine, tamarack, & fir. Good grass in open glades.
	E. on true line along S. Bdy. of Secs. 33. Var. 19°10'E.