

Resurvey W. Bdy., T.5 S., R.33 $\frac{1}{2}$ E., W. M.

Chains	N. on W. Bdy. of Sec. 34.
	Var.19°30'E.
17.28	The Cor. to Tp. 5 S., R.33 E.
30.78	Spring branch, 3 lks. wide, runs N.E., 250 ft. below last Cor. Ascend along hillside.
55.00	Top of ridge, brs. E. & W., 150 ft. high. Descend.
57.02	The $\frac{1}{4}$ Sec. Cor.
69.00	Foot of hill, 200 ft. below ridge & ascend.
80.00	Set post, 4 ft. long, 4 ins. sq., in stony ground, piled stone around post, for Cor. to Secs. 27 & 34, marked T.5 S., R.33 $\frac{1}{2}$ E. on E. S.27 on N. and S.34 on S., with 1 notch on S. and 5 notches on N. edges, from which A fir, 18 ins. diam., brs. N.42°E., 55 lks. dist., marked T.5 S., R.33 $\frac{1}{2}$ E., S.27, B.T. A pine, 18 ins. diam., brs. S.12°E., 54 lks. dist., marked T.5 S., R.33 $\frac{1}{2}$ E., S.34, B.T. Land; hilly & mountainous. Soil; 2nd & 3rd rate. Heavily timbered with pine, fir & tamarack. Dense undergrowth of pine & fir.
	N. on W. Bdy. of Sec. 27.
	Var.19°15'E.
	Ascend.
16.80	The Cor. to Secs. 25 & 36, which is a basalt stone, 14 x 12 x 5, marked with 1 notch on S. and 5 notches on N. edges, from which A fir, 24 ins. diam., brs. N.60°E., 55 lks. dist., marked T.5 S., R.34 E., S.30, B.T. A pine, 12 ins. diam., brs. S.68°E., 98 lks. dist., marked T.5 S., R.34 E., S.31, B.T. A pine, 5 ins. diam., brs. S.45°W., 10 lks. dist., marked T.5 S., R.33 E., S.36, B.T. A pine, 10 ins. diam., brs. N.85°W., 50 lks. dist.,