

Resurvey W. Bdy., T.5 S., R.33 $\frac{1}{2}$ E., W. M.

Chains	
	<p>marked T.5 S., R.33 E., S.25, B.T.</p> <p>Destroyed marks referring to Secs. 30 & 31.</p>
26.00	Top of ridge, 100 ft. above Cor. to Secs. 30 & 31.
56.50	The $\frac{1}{4}$ Sec. Cor.
62.55	Creek, 20 lks. wide, runs N.W., in ravine, 300 ft. deep.
	And ascend.
80.00	Set basalt stone, 24 x 12 x 6 ins., 18 ins. in ground, for Cor. to Secs. 22 & 27, marked with 2 notches on S. and 4 notches on N. edges, with mound of stone alongside.
	Land; mountainous.
	Soil; 2nd & 3rd rate.
	Heavily timbered with pine, fir & tamarack.
	N. on W. Bdy. of Sec. 22.
	Var. 19°20'E.
16.20	The Cor. to Secs. 24 & 25, which is a basalt stone, 20 x 12 x 10 ins., marked with 4 notches on N. and 2 notches on S. edges, with mound of stone alongside, from which
	A pine, 18 ins. diam., brs. N.46°E., 245 lks. dist., marked T.5 S., R.33 E., S.19, B.T.
	A pine, 12 ins. diam., brs. S.18°W., 158 lks. dist., marked T.5 S., R.33 E., S.25, B.T.
	Destroyed marks referring to Secs. 19 & 30
52.50	Enter open glade.
56.20	The $\frac{1}{4}$ Sec. Cor.
68.20	Spring branch, course N.W. Enter scattering timber.
80.00	Set basalt stone, 18 x 12 x 6 ins., 12 ins. in ground, for Cor. to Secs. 15 & 22, marked with 3 notches on N. & S. edges, from which
	A pine, 6 ins. diam., brs. N.18°E., 18 lks. dist., marked T.5 S., R.33 $\frac{1}{2}$ E., S.15, B.T.
	And raised mound of stone alongside.
	Land; mountainous.
	Soil; 2nd & 3rd rate.
	Heavily timbered with pine, fir & tamarack, partially deadened by fire.
	Oct. 12, 1882.