

Subdivisional Lines, T.5 S.,R.33 E.,W. M.

Chains	
	E. on random line bet. Secs. 10 & 15. Var.19°30'E.
33.50	Spring branch, course N. Descent about 150 ft.
40.00	Set temp. 1/4 Sec. Cor.
79.78	Intersected N. & S. line, 38 lks. N. of Cor. to Secs. 10, 11, 14 & 15, from which Cor., I run N.89°44'W. on true line bet. Secs. 10 & 15. Var.20°45'E.
39.89	Set basalt stone, 14 x 12 x 8 ins., 10 ins. in ground, for 1/4 Sec. Cor., on level, marked 1/4 on N. face, from which A tamarack, 16 ins. diam., brs. N.54°W., 40 lks. dist., marked 1/4 S., B.T. A pine, 26 ins. diam., brs. S.54°E., 47 lks. dist., marked 1/4 S., B.T.
79.78	The Cor. to Secs. 9, 10, 15 & 16. Land; surface rolling. Soil; 3rd & 2nd rate. Mostly open; some pine & tamarack timber, very scattering.
<hr/>	
	N. bet. Secs. 9 & 10. Var.19°30'E. Slightly descending.
37.50	Spring branch, course N.W. Descent 100 ft.
40.00	A pine, 9 ins. diam., on S.W. slope, for 1/4 Sec. Cor., marked 1/4 S. on W. side A pine, 5 ins. diam., brs. N.71°E., 74 lks. dist., marked 1/4 S., B.T. A pine, 10 ins. diam., brs. N.86°W., 36 lks. dist., marked 1/4 S., B.T.
80.00	Set basalt stone, 15 x 10 x 5 ins., 10 ins. in ground, on W. hillside, for Cor. to Secs. 3, 4, 9 & 10, marked with 5 notches on S. and 3 notches on E. edges. A pine, 10 ins. diam., brs. S.14°E., 121 lks. dist., marked T.5 S., R.33 E., S.10, B.T. A pine, 18 ins. diam., brs. S.66°W., 105 lks. dist., marked T.5 S., R.33 E., S.9, B.T.