

## Subdivisional Lines, T.5 S., R.33 E., W. M.

Chains	
	marked $\frac{1}{4}$ S., B.T.
	A pine, 18 ins. diam., brs. S.85°W., 24 lks. dist.,
	marked $\frac{1}{4}$ S., B.T.
80.04	The Cor. to Secs. 17, 18, 19 & 20.
	Land; surface broken.
	Soil; 2nd & 3rd rate.
	Some open pine & tamarack timber, mostly on E. $\frac{1}{2}$ mile, W. $\frac{1}{2}$
	mile mostly open, only a few scattering trees, except
	along spring branch.
	<hr/>
	W. on random line bet. Secs. 18 & 19.
	Var. 18°15'E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
78.84	Intersected W. Bdy., 78 lks. N. of Cor. to Secs. 18 & 19,
	which is a post and stone, in mound of stone, in open
	prairie, on slight N.W. slope, from which, I run
	N.89°27'E. on true line bet. Secs. 18 & 19.
	Var. 19°30'E.
38.84	Set basalt stone, 18 x 8 x 7 ins., 12 ins. in ground, on
	level, in grove, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face.
	A pine, 18 ins. diam., brs. N.22°E., 52 lks. dist.,
	marked $\frac{1}{4}$ S., B.T.
	A pine, 22 ins. diam., brs. S.42°W., 106 lks. dist.,
	marked $\frac{1}{4}$ S., B.T.
78.84	The Cor. to Secs. 17, 18, 19 & 20.
	Land; surface undulating.
	Soil; 2nd & 1st rate.
	A grove of pine timber at and around $\frac{1}{2}$ mile Cor. Remainder
	nearly all open prairie; good grass; good farming land.
	<hr/>
	N. bet. Secs. 17 & 18.
	Var. 18°15'E.
24.00	Enter strip of open timber, course N.W. & S.E.
39.75	Spring branch, course N.W.
40.00	Set basalt stone, 18 x 12 x 5, on level near spring branch
	for $\frac{1}{4}$ Sec. Cor., 12 ins. in ground, marked $\frac{1}{4}$ on W. face.