

Chains	
	<p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine & fir.</p> <p>Dense undergrowth of pine & fir.</p>
	<p>W. on S. Bdy. of Secs. 35.</p> <p style="text-align: right;">Var.20°E.</p> <p>Descend.</p>
17.80	Creek, 12 lks. wide, runs N., 350 ft. belo Sec. Cor. Ascend from creek.
22.00	Top of sharp ridge, brs. N. & S., 150 ft. high & descend.
27.00	Brook, 4 lks. wide, runs N. Ascend from brook.
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S.,SC. on N. face, from which</p> <p style="padding-left: 40px;">A pine, 4 ins. diam., brs. N.70°W., 47 lks. dist., marked $\frac{1}{4}$ S.,B.T.</p> <p style="padding-left: 40px;">▲ tamarack, 30 ins. diam., brs. S.55°E., 35 lks. dist., marked $\frac{1}{4}$ S.,B.T.</p>
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for standard Cor. to Secs. 34 & 35, marked</p> <p style="padding-left: 40px;">S.C.; T.5 S.,R.33$\frac{1}{2}$ E. on N.</p> <p style="padding-left: 40px;">S.35 on E. and</p> <p style="padding-left: 40px;">S.34 on W. faces, with</p> <p style="padding-left: 40px;">2 notches on E. and</p> <p style="padding-left: 40px;">4 notches on W. edges, from which</p> <p style="padding-left: 40px;">A pine, 24 ins. diam., brs. N.50°E., 26 lks. dist., marked T.5 S.,R.33$\frac{1}{2}$ E.,S.35,B.T.</p> <p style="padding-left: 40px;">A pine, 24 ins. diam., brs. N.58°W., 24 lks. dist., marked T. 5 S.,R.33$\frac{1}{2}$ E.,S.34,B.T.</p> <p style="padding-left: 40px;">▲ pine, 20 ins. diam., brs. S.70°W., 20 lks. dist., marked T.6 S.,B.T.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine & fir, 80 chs.</p> <p>Dense undergrowth of pine & fir, 80 chs.</p>