

Subdivisional Lines, T.5 S., R.33 $\frac{1}{2}$ E., W. M.

Chains 9.00	A ravine, course N.W.
	Thence descending along hillside, facing S.W.
40.00	To point on top of hill.
	Set pine post, 3 ft. long, 3 ins. sq., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which
	A fir, 20 ins. diam., brs. N.32°W., 22 lks. dist., marked $\frac{1}{4}$ S., B.T.
	A pine, 4 ins. diam., brs. S.75°E., 20 lks. dist., marked $\frac{1}{4}$ S., B.T.
50.00	Descend abruptly E. & W.
73.00	Foot of hill.
	Hidaway Creek, 10 lks. wide, runs W.
80.00	Set tamarack post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 26, 27, 34 & 35, marked
	T.5 S., S.26 on N.E.
	R.33 $\frac{1}{2}$ E., S.35 on S.E.
	S.34 on S.W. and
	S.27 on N.W. faces, with
	1 notch on S. and
	2 notches on E. edges, from which
	A pine, 27 ins. diam., brs. S.10°E., 14 lks. dist., marked T.5 S., R.33 $\frac{1}{2}$ E., S.35, B.T.
	A pine, 8 ins. diam., brs. S.34°W., 25 lks. dist., marked T.5 S., R.33 $\frac{1}{2}$ E., S.34, B.T.
	A pine, 30 ins. diam., brs. N.28°W., 7 lks. dist., marked T.5 S., R.33 $\frac{1}{2}$ E., S.27, B.T.
	A fir, 8 ins. diam., brs. N.69°E., 34 lks. dist., marked T.5 S., R.33 $\frac{1}{2}$ E., S.26, B.T.
	Land; mountainous.
	Soil; 2nd rate.
	Heavily timbered with pine, fir & tamarack.
	Dense undergrowth of pine, fir & tamarack.
	Oct. 28, 1882.
	E. on random line bet. Secs. 26 & 35.
	Var. 20°E.