

Subdivisional Lines, T.5 S., R. 33 $\frac{1}{2}$ E., W. M.

Chains	<p>Land; rolling.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir & tamarack.</p> <p>Dense undergrowth of pine, fir & tamarack, partly pine grass.</p>
	<p>E. on random line bet. Secs. 14 & 23.</p> <p style="text-align: right;">Var. 20°E.</p>
	<p>Over rolling ground.</p> <p>Through timber.</p>
14.00	A ravine, course N.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor., thence gently descending, over rolling ground to
70.25	A ravine, course N. and ascending gently.
79.60	A wagon road, course N. & S.
80.13	Intersect the N. & S. line at Cor. to Secs. 13, 14, 23 & 24.
	Thence I run
	<p>W. on true line bet. Secs. 14 & 23.</p> <p style="text-align: right;">With same Var.</p>
40.07	<p>Set basalt stone, 13 x 10 x 8 ins., 9 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which</p> <p>A pine, 36 ins. diam., brs. N. 80°W., 49 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>A fir, 13 ins. diam., brs. S. 51°W., 65 lks. dist., marked $\frac{1}{4}$ S., B.T.</p>
80.13	The Cor. to Secs. 14, 15, 22 & 23.
	Land; rolling.
	Soil; 3rd rate.
	Heavily timbered with pine, fir & tamarack.
	Dense undergrowth of pine brush & pine grass.
	<p>W. on random line bet. Secs. 15 & 22.</p> <p style="text-align: right;">Var. 20°E.</p>
	Through timber.
22.62	Intersect the W. Bdy. of Tp., 10 lks. S. of Cor. to Secs.