

South Bdy., T 5 S R 34 E W M.

Chains	<p>with 1 notch on E. and 5 notches on W. faces, from which</p> <p>A pine, 8 ins. diam., brs. N.56°E., 28 lks. dist., marked T 5 S R 34 E S 36 B T.</p> <p>A pine, 12 ins. diam., brs. N.59°W., 59 lks. dist., marked T 5 S R 34 E S 35 B T.</p> <p>Land; high, broken and mountainous. Soil; rocky, gravelly, 4th rate. Timber; pine, fir & tamarack.</p>
	<p>W. on S. Bdy. of Sec. 35. Var.20°E.</p> <p>Ascend through black pine timber. undergrowth of same and down timber.</p> <p>8.50 Rock, 10 x 15 x 10 ft. high brs. N.30 lks.</p> <p>22.00 Bluff of rocks, 50 ft. high, brs. N. Ascend through open pine timber.</p> <p>35.00 Descend through thick timber.</p> <p>40.00 Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground, on S.W. hillside, 50 ft. from summit, for Standard ¼ Sec. Cor., marked ¼ S S C on N. face; from which</p> <p>A pine, 4 ins. diam., brs. N.40°E., 40 lks. dist., marked S C ¼ S B T.</p> <p>A pine, 12 ins. diam., brs. N.59°W., 59 lks. dist., marked S C ¼ S B T.</p> <p>Descend through thick pine & tamarack.</p> <p>45.00 Center of hollow, course S.E. Ascend through dense black pine & fallen timber.</p> <p>77.50 Enter table land, densely covered with black pine.</p> <p>80.00 A pine tree, 4 ins. diam., which I marked for Standard Cor. to Secs. 34 & 35; S C T 5 S R 34 E on N., S 35 on E. and S 34 on W. faces, with 2 notches on E. and 4 notches on W. faces; from which</p> <p>A tamarack, 22 ins. diam., brs. N.39°W., 36 lks. dist., marked T 5 S R 34 E S 34 B T.</p> <p>A pine, 3 ins. diam., brs. N.70°E., 22 lks. dist., marked T 5 S R 34 E S 35 B T.</p> <p>Land; high, broken and mountainous. Soil; rocky, gravelly 4th rate. Timber; fir, pine & tamarack.</p>
	<p>W. on S. Bdy. of Sec. 34. Var.20°E.</p> <p>Descend through dense black pine, heavy, scattering & fallen poles.</p>