

Subdivisional Lines, T.5 S.,R.34 E.,W. M.

Chains

3 notches on S. & E. edges, from which

A pine, 8 ins. diam., brs. S.17°W., 54 lks. dist.,
marked T 5 S R 34 E S 21 B T.

A fir, 5 ins. diam., brs. S.32°E., 15 lks. dist.,
marked T 5 S R 34 E S 22 B T.

A tamarack, 6 ins. diam., brs. N.23°W., 43 lks. dist.,
marked T 5 S R 34 E S 16 B T.

A pine, 5 ins. diam., brs. N.47°E., 49 lks. dist.,
marked T 5 S R 34 E S 15 B T.

Land; high and mountainous.

Soil; 2nd & 3rd rate.

Heavily timbered with pine, fir & tamarack and

Dense undergrowth of same woods, 77.30 chs.

N. bet. Secs. 15 & 16.

Var.20°45'E.

40.00 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$
Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which

A pine, 5 ins. diam., brs. S.21°W., 24 lks. dist.,
marked $\frac{1}{4}$ S B T.

A pine, 5 ins. diam., brs. S.21°E., 64 lks. dist.,
marked $\frac{1}{4}$ S B T.

61.00 Enter bottom brs. E. & W.

62.10 Creek, 10 lks. wide, runs E.

64.00 Leave bottom brs. E. & W.

71.25 Spring, 8 lks. W. of line runs S.

80.00 Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for
Cor. to Secs. 9, 10, 15 & 16, with mound of stone around
post, marked

T 5 S S 10 on N.E.

R 34 E S 9 on N.W.

S 16 on S.W. and

S 15 on S.E., with

4 notches on S. and

3 notches on E. edges,