

Subdivisional Lines, T.5 S., R.34 E., W. M.

Chains	
62.00	Head of ravine, course N.W.
65.00	Wagon road brs. N. & S.
80.00	Intersect N. & S. line at Cor. to Secs. 3, 4, 9 & 10.
	Thence I run
	W. on true line bet. Secs. 4 & 9.
40.00	Set basalt stone, 18 x 15 x 4, 12 ins. in ground, for $\frac{1}{4}$
	Sec. Cor., marked $\frac{1}{4}$ on N. face, from which
	A pine, 24 ins. diam., brs. N.53°E., 32 lks. dist.,
	marked $\frac{1}{4}$ S B T.
	A tamarack, 18 ins. diam., brs. S.27°E., 41 lks. dist.,
	marked $\frac{1}{4}$ S B T.
80.00	The Cor. to Secs. 4, 5, 8 & 9.
	Land; mountainous.
	Soil; good 2nd rate.
	Heavily timbered with pine & tamarack and
	Dense undergrowth of same kinds of wood.
	N. on random line bet. Secs. 4 & 5.
	Var. 21°10'E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
68.00	Small ravine, course N.W.
80.20	Intersect N. Bdy. of Tp., 49 lks. W. of Cor. to Secs. 32,
	33, 4 & 5, which is a basalt stone, 15 x 12 x 7, 10 ins.
	in ground, marked with 4 notches on E. and 2 notches on
	W. edges, from which
	A pine, 14 ins. diam., brs. N.49°E., 82 lks. dist.,
	marked T 4 S R 34 E S 33 B T.
	A pine, 8 ins. diam., brs. N.68°W., 175 lks. dist.,
	marked T 4 S R 34 E S 32 B T.
	A pine, 42 ins. diam., brs. S.43°W., 57 lks. dist.,
	marked T 5 S R 34 E S 5 B T.
	A pine, 40 ins. diam., brs. S.28°E., 167 lks. dist.,
	marked T 5 S R 34 E S 4 B T.
	Thence I run
	S.21°W. on true line bet. Secs. 4 & 5.