

Subdivisional Lines, T.5 S., R.34 E., W. M.

Chains	
	<p>A pine, 9 ins. diam., brs. S.43°W., 19 lks. dist., marked $\frac{1}{4}$ S B T.</p>
80.25	<p>The Cor. to Secs. 29, 30, 31 & 32. Land; high & mountainous. Soil; 2nd rate. Heavily timbered with pine, tamarack & fir and Dense undergrowth of same woods. Oct. 24, 1882.</p>
	<p>N.W. bet. Secs. 29 & 30.</p>
	<p>Var. 21°E.</p>
	<p>Descend.</p>
12.25	<p>Brook, 3 lks. wide, in ravine, runs N.W.</p>
23.80	<p>Brook, 2 lks. wide, runs W., 300 ft. below Sec. Cor.</p>
	<p>Ascend.</p>
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face, from which A pine, 9 ins. diam., brs. S.80°E., 6 lks. dist., marked $\frac{1}{4}$ S B T. A pine, 9 ins. diam., brs. N.48°W., 27 lks. dist., marked $\frac{1}{4}$ S B T.</p>
68.00	<p>Top of ridge, brs. E. & W., 300 ft. above last noted brook.</p>
	<p>And descend.</p>
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, on steep hillside, slopes N., 300 ft. below top of hill, for Cor. to Secs. 19, 20, 29 & 30, marked T 5 S S 20 on N.E. R 34 E S 19 on N.W. S 30 on S.W. and S 29 on S.E. faces, with 2 notches on S. and 5 notches on E. edges, from which A pine, 4 ins. diam., brs. S.46°W., 11 lks. dist., marked T 5 S R 34 E S 30 B T. A pine, 4 ins. diam., brs. N.40°W., 28 lks. dist., marked T 5 S R 34 E S 29 B T.</p>