

Subdivisional Lines, T.5 S., R.34 E., W. M.

Chains

from which

A tamarack, 20 ins. diam., brs. N.8°E., 50 lks. dist.,
marked T 5 S R 34 E S 18 B T.

A tamarack, 12 ins. diam., brs. S.5°E., 125 lks. dist.,
marked T 5 S R 34 E S 19 B T.

A pine, 12 ins. diam., brs. S.57°W., 120 lks. dist.,
marked T 5 S R 33½ E S 24 B T.

A fir, 8 ins. diam., brs. N.60°W., 35 lks. dist.,
marked T 5 S R 33½ E S 13 B T.

Thence I run

S.89°50'E. on true line bet. Secs. 18 & 19.

Var. 20°30'E.

40.50 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for ¼
Sec. Cor., marked ¼ S on N. face, from which

A tamarack, 20 ins. diam., brs. N.19°W., 62 lks. dist.,
marked ¼ S B T.

A fir, 24 ins. diam., brs. S.45°W., 26 lks. dist.,
marked ¼ S B T.

80.50 The Cor. to Secs. 17, 18, 19 & 20.

Land; high & mountainous.

Soil; 2nd rate.

Heavily timbered with pine, fir & tamarack and

Dense undergrowth of same kinds of wood.

N. bet. Secs. 17 & 18.

Var. 21°E.

27.00 Spring branch, 2 lks. wide, runs N.E.

40.00 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for
¼ Sec. Cor., marked ¼ S on W. face, from which

A pine, 8 ins. diam., brs. S.73°E., 10 lks. dist.,
marked ¼ S B T.

A pine, 8 ins. diam., brs. S.63°W., 15 lks. dist.,
marked ¼ S B T.

65.00 Enter marsh, brs. E. & W.

66.00 Leave marsh, brs. E. & W.