

Resurvey West Bdy., T 6 N R 31 E W M.

Chains	<p>ground. No trace of the old post to be found.</p> <p>By reference to the stumps of the original bearing trees, I relocate the original position of the Cor., at which point, I</p> <p>Set a juniper post, 3 ft. long, 4 ins. sq., 24 ins in ground for Cor. of Tps 5 & 6 N Rs 30 & 31 E., mkd.</p> <p style="padding-left: 40px;">T 6 N S 31 on N.E.</p> <p style="padding-left: 40px;">R 31 E S 6 on S.E.</p> <p style="padding-left: 40px;">T 5 N S 1 on S.W. and</p> <p style="padding-left: 40px;">R 30 E S 36 on N.W. faces, with</p> <p style="padding-left: 40px;">6 notches on each edge;</p> <p>from which</p> <p style="padding-left: 40px;">A juniper, 6 ins. diam., brs. S.78° E., 485 lks. dist., marked T 5 N R 31 E S 6 B T.</p> <p style="padding-left: 40px;">A juniper, 6 ins. diam., brs. N.5°30' E., 261 lks. dist., marked T 6 N R 31 E S 31 B T.</p> <p style="padding-left: 40px;">No other trees available; dig pits, 24 x 24 x 12 ins. on each line, N., E. & W., 4 ft. and S. of post 8 ft. dist.; raised mound of earth, 5 ft. base, 2½ ft. high, S. of Cor. From this Tp. Cor. the (Latitude is 45°57' N. (Longitude 119°00' W.</p> <p>Thence I run</p> <p>N.0°18' E., resurveying the W. Bdy. of Sec.31.</p> <p>Descending from Cor., thru scattering timber.</p> <p>11.60 Leave scattering timber & enter loose, sandy land; brs. E. & W.</p> <p>20.75 Enter flat bottom of Juniper Canyon, 400 ft. below Tp. Cor., course West.</p> <p>22.25 Ascend.</p> <p>26.78 A wire fence brs. N.W. & S.E.</p> <p>34.50 Bottom of ravine, course S.W.</p> <p>39.28 To the old ¼ Sec. Cor., which I now destroy & reestablish at the same point as follows:</p> <p style="padding-left: 40px;">Set basalt stone, 16 x 12 x 10 ins., 10 ins. in ground, for ¼ Sec. Cor., mkd. ¼ on E. face & raise mound of stone, 2 ft. base, 1½ ft. high, W. of Cor.; pits impracticable.</p> <p>Thence from the ¼ Sec. Cor., I run</p>
--------	---