

Resurvey West Bdy., T 6 N R 31 E W M.

Chains	
	Thence I run
	N. resurveying W. Bdy. of Sec. 19.
.10	Dry channel of creek, 10 lks. wide, course W.
2.00	Dry bed of creek, 15 lks. wide, course W.
4.00	Wire fence brs. N.E. & S.W. & enter field.
8.00	Fence brs. E. & W. & enter barnyard.
8.25	S.D.Tucker's barn brs. W., 100 lks. dist.
9.75	S.D.Tucker's house brs. W. 3.00 chs. dist.
10.44	Fence brs. N.W. & S.E.
10.60	Road to Clover Hill brs. E. & W.
10.85	Fence brs. N.W. & S.E. & enter field.
19.86	Fence brs. N.34°E. and S. 34° W.; leave field & enter road-way.
20.53	O.W.R. & N. R.R.Co's. right of way fence brs. N.34° E. & S.34° W.
22.19	East rail of side track of R.R.; beginning of switch.
22.53	East rail of main track of O.W.R. & N. R.R. brs. N.34° 38' E. and S.34°38' W.
24.68	Right of way fence parallel to track and enter field.
25.68	Leave field & enter sagebrush, brs. N.E. & S.W.
26.90	At this point, I make diligent search for the Meander Cor. established by Deputy Walden in 1874; all evidence of which has entirely disappeared.
28.00	To the left bank of Columbia River.
	Set basalt stone, 24 x 16 x 14 ins., 18 ins. in ground, for Meander Cor. of fractl. Secs. 19 & 24, mkd. M C on N., T 6 N on S., R 30 E S 24 on W. and R 31 E S 19 on E. face; dig pit, 36 x 36 x 12 ins., 8 ft. S. of stone & raise mound of earth, 4 ft. base, 2 ft. high, S. of Cor.
	Land; level & rolling.
	Soil; sandy, 1st & 2nd rates.
	No timber.
	Undergrowth; sage.