

Exterior Lines, T 6 N R 31 E W M.,
 As surveyd by W.H.Odell, U.S. Deputy Surveyor,
 Under Contract No. 110,
 Dated Feby. 2, 1865.

Chains

N. bet. Rs. 31 & 32 E., T 6 N. on E. Bdy. of Sec.36.

Var.19°30'E.

40.00 Set $\frac{1}{4}$ Sec. post Cor., on E. side of deep ravine, sloping
 to the N.W.

80.00 Set post Cor. for Secs. 25, 26, 30 & 31, on top of high
 table land. Drove charred stake, dug pits & raised
 mound, as per instructions.

Land; broken.

Good grass.

Soil; 2nd rate.

N. on E. Bdy. of Secs. 25.

Var.21°15' E.

40.00 Set $\frac{1}{4}$ Sec. post on S. side of large ravine; drove charred
 stake; dug pits & raised mound, as per instructions.

55.00 Bottom of ravine, course S.W.

80.00 Set post Cor. for Secs. 24, 25, 19 & 30; drove charred
 stake; dug pits & raised mound, as per instructions.

Soil; 2nd rate.

Land; broken.

N.on E. Bdy. of Sec. 24.

Var. 21°30'E.

40.00 Set $\frac{1}{4}$ Sec. post in small gulch, course S.15° E. Drove
 charred stake; dug pits & raised mound, as per instruc-
 tions.

80.00 Set post Cor. for Secs. 13, 24, 18 & 19, in head of gully,
 course S.E. Drove charred stake; dug pits & raised mound,
 as per instructions.

Land; broken.

Grass; good.

Soil; 2nd rate.

N. on E. Bdy. of Secs. 13.

Var.20°30' E.